BANGALORE DIVISION.

Dated 6th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 20th May 1929, for constructing Women's Dispensary, Mysore Lancers, Hebbal, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3(a). Percentages less or above estimated rates will not be accepted.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Women's Dispensary, Mysore Lancers, Hebbal, Bangalore in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor, will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be ferfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for the Women's Dispensary, Mysore Lancers.

Sl. No.	Items of work	Quantity	Unit	Rate
1	Earthwork excavation foundation and filling basement level.	195	C.yd.	
2	Stone jelly concrete in chunam	1,567	C.ft.	
3	Burnt stone in clay for foundation	2,525	,,	
4	Do do	1,784	,,	
5	Burnt brick in clay	4,001	,,	
6	Burnt brick in chunam	1,391	,,	
7	Burnt stone slabs 5″×6″ thick with one line dressing top and side wherever necessary.	1,216	S.ft.	
8	Plastering with chunam	118·56	Sqr.	
9	Flooring with Cuddapa slabs 1½″ on 3″ concrete bed and cement pointing.	16·90	,,	
10	Flooring with Marsceilles tiles on 3″ to 4″ concrete bed and cement pointing.	4·34	,,	
11	Burnt stone pillars with nice dressing (1′×1′) with caps and base (1½′×1½′) as per design of existing pillars in hospital.	11	No.	
12	Do do half pillars	3	,,	
13	Teakwood shelf planks in store 1″ thick ...	72	S.ft.	
14	Teakwood pegs with fixing	16	No.	
15	Steel girders and joists with fixing . ..	80·50	Cwt.	
16	Burnt slabs for (wall plates)	295	R.ft.	
17	Jack arch roof	20·48	Sqr.	
18	Cornice (9″×9″)	395	R.ft.	
19	Parapet wall 9″ thick with coping 1½′ height ...	292	,,	
20	Teakwood work wrought and put up with wood oiling complete.	40·06	C.ft.	
21	Roofing with 1st class Mangalore tiles on teak reepers 2″×1″,	15·01	Sqr.	
22	Teakwood ornamental eave board 9″×1″ ...	16	R.ft.	
23	First class Mangalore ridge tiles set in mortar and cement, pointing.	68	,,	
24	Chunam border over roof 9″ x 6″ with brick in chunam and plastering over.	84	,,	
25	Teakwood windows with panelled shutters, etc., complete.	333	S.ft.	
	Teakwood doors with panelled shutters, etc., complete.	663	,,	

Sl. No.	Items of work	Quantity	Unit	Rate
27	Teakwood doors with battened shutters with frame etc., complete.	23	S.ft.	
28	Teakwood windows with battened shutters, iron bars etc., complete.	54	,,	
29	Teakwood ventilators with glazed shutters and expanded metal, complete.	219	,,	
30	Chacolate painting 3 coats	29·63	Sqr.	
31	White lead painting to walls	11·13	,,	
32	White washing	118·56	,,	
33	Cement pointing to basement	6·73	,,	
34	Coping with burnt brick in chunam and cement plastering over.	199	R.ft.	
35	Masonry finials to gate pillars with cornice, etc. ...	2	No.	
36	Teakwood gate with iron bars, complete ...	48	S.ft.	
37	Iron holds with lead, etc.	4	No.	
38	Fixing the above hold fast in lead including drilling holes, etc.	4	,,	
39	Removing doors and window in the old wall ..	2	,,	
40	Fixing the above door in the place of a window removed including and dismantling the wall, etc., complete.	1	,,	
41	Chunam plastering to Mangalore tiled roof ...	8·78	Sqr.	
42	Teakwood finials to gate	4	No.	
43	Teakwood pendent	12	,,	

H. R. VENKATASUBBA RAO,
Executive Engineer.

MYSORE DIVISION.

Dated 30th April—2nd May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 3 P.M., on 28th May 1929, for Restoring Hatna Tank (Minor) Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division, Mysore, between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 (two hundred and fifty only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Hatna (Minor) Tank, Nagamangala Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

Abstract estimate for "Restoring Hatna Minor Tank, Register No. Nil of Nagamangala Taluk:—

Serial No.	Items of work	Per	Quantity
	BUND.		
1	Clearing jungle and rubbish, etc., on the bund with cutting grips and steps.	Lump	sum
2	Earthwork to bund with watering and tamping ...	C.yd.	7,996
3	Gravel backing to revetment (9" thick)	,,	317
4	New rough stone revetment with jelly backing ...	,,	982
5	Turfing to slopes of bund	Sqrs	282·90
6	Providing and fixing grade stones including cutting figures and painting.	No.	13
7	Providing and fixing Index stones	,,	13
8	Do. Bench mark stones	,,	2
9	Providing and fixing Reg. No. stones with date ...	,,	1
10	Do Guage stones	,,	1
	BREACH.		
1	Removing silt and sand in the breach	C.yd.	1,800
2	Excavating foundation of trench in soft and hard rock ...	,,	16
3	Benching soft rock	S.ft.	1,450
4	Cutting steps and grips on sides of breach	Lump	sum
5	Earthwork for filling in the breach with a mixture of good gravel and clay in equal proportion with watering and tamping.	C.yd.	10·901
6	Puddle wall	,,	915
7	Gravel backing to revetment	,,	306
8	Rough stone revetment with jelly backing	,,	1,220
9	Burnt brick or stone in surki mortar	C.ft.	1,305
10	Plastering or pointing in surki mortar	Sqr.	8·70
11	Turfing the slopes of bund	,,	83·50
	SLUICE No. I AND II.		
1	Earthwork excavation hard soil	C.yd.	102
2	Concrete in broken stones in surki mortar	C.ft.	507
3	Burnt brick in surki mortar	,,	1,014
4	Burnt stone slabs 6" thick dressed and fixed	S.ft.	318
5	Surki plastering	Sqs.	10·51
6	Boring holes in slabs for plug, etc. — ...	No.	4
7	Providing one wooden plug to size with rod chain and locking arrangement.	,,	1
8	Filling earth with watering and tamping ...	C.yd.	102
	LEFT WASTE WEIR.		
1	Earthwork excavation hard gravelly soil	C.yd.	131
2	Surki concrete in broken stones in surki mortar ...	C.ft.	854
3	Burnt brick in surki mortar	,,	1,267
4	Burnt stone slabs 6" thick dressed and fixed	S.ft.	413
5	Joggle joints to the coping slabs of body wall... ...	No.	20
6	Surki mortar plastering	Sqr.	17·39
7	Rough stone work new with jelly backing	C.yd.	160
8	Approach and draft clearing	Lump	sum

N. G. KRISHNA IYENGAR,
Executive Engineer.
6 I